



Walschon Fire Protection, Inc.

2178 Rheem Drive, Suite A, Pleasanton, CA 94588 • LIC. #568438 • tel. (650) 594-1588 • fax (650) 594-1613

QUOTATION: AUTOMATIC FIRE SPRINKLERS

TO: Joel Cadiz DATE: July 24, 2017
COMPANY: San Mateo-Foster City School District ESTIMATE # 892-17
PROJECT NAME: Fire System Repairs
PROJECT LOCATION: Sunnybrae Elementary School, 1031 S. Delaware Street, San Mateo

Estimate Prepared by Jason Hudgins Cell: (925) 580-0053
PRICE BASED ON Five-Year inspection report dated 7/18/17
TYPE OF WORK Repair
PRICE INCLUDES Union labor and materials (tax included)

We propose to provide all labor & materials to perform the following scope of work at the above referenced project for the amount of **\$23,886.⁰⁰** (Pricing breakdown: Labor \$14,604 / Materials \$9,282)

SCOPE OF WORK

Kindergarten

1. Replace (32) loaded/painted Viking brass 200 degree QR SSUs, classrooms 1 & 2
2. Replace (22) loaded Tyco brass 200 degree SR SSUs, outside under eve of building
3. Provide and install (1) PIV identification sign
4. Provide and install (1) FDC identification sign
5. Provide and install (2) OS&Y identification signs
6. Copy client supplied hydraulic information to dataplate, affix to riser

LGI Building

7. Replace (7) painted Viking Chrome 155 degree QR SSPs at stage and chalkboard
8. Replace (20) loaded Viking chrome 155 degree QR SSPs, under lower mezzanine area
9. Replace (2) loaded/damaged Viking chrome 155 degree QR SSPs, kitchen area
10. Replace (2) painted Viking chrome 155 degree QR SSPs, storage area to right of kitchen doors
11. Replace (3) painted 200 degree Viking Qr SSUs, above ceiling by double doors facing Kindergarten
12. Copy client supplied hydraulic information to dataplate, affix to riser

Library

13. Provide and install (1) white 401 trim outside storage closet
14. Replace (3) loaded Viking chrome 155 degree QR SSPs, computer lab

Main Building

15. Replace (6) loaded SSPs in CR12
16. Replace (6) loaded SSPs in CR11
17. Replace (8) loaded SSPs in CR10
18. Replace (6) loaded SSPs in CR9
19. Replace (4) loaded SSPs in CR8
20. Replace (1) painted SSP above heating unit, also provide/install trim
21. Replace (15) loaded SSPs in administration offices center of building
22. Replace (3) loaded SSPs in CR7
23. Replace (3) loaded SSPs in CR6
24. Replace (6) loaded SSPs in CR5
25. Replace (1) painted SSU in CR4 storage closet
26. Replace (6) loaded SSPs in CR3
27. Replace (24) painted SSPs, provide/install (24) escutcheons, one in each classroom 1st and 2nd floor above heater units
28. Replace (1) painted SSU directly across from classroom 26 in storage room
29. Replace (1) damaged SSP in CR26
30. Replace (2) loaded SSPs in CR26
31. Replace (4) loaded SSPs in CR27
32. Replace (3) loaded SSPs in CR28
33. Replace (6) loaded SSPs in CR29
34. Replace (2) loaded SSPs in CR30
35. Replace (4) loaded SSPs in CR31
36. Replace (1) loaded SSP in CR32

