

Commercial Plumbing & Building
851 N 15th st
San Jose CA 95112
408-449-0680

estimate

DATE	ESTIMATE #
6/2/2020	1551

BILL TO
Milpitas School District 1331 East Calaveras Milpitas, CA 95035

SHIP TO
Spangler Elementary School 140 N Abbott Ave Milpitas CA 95035

P.O. #	DUE DATE
	7/2/2020

ITEM	DESCRIPTION	QTY	RATE	AMOUNT
	<i>We will replace approximately 190 feet of 4" Cast iron drain pipe and 190' of 1" copper in front existing portables. Including Clean out& fittings. (Plan calls for 0.3% fall. Min by code is 1.0% this could lead to problems in the future)We will replace Approx. 90' of Clay pipe with 4" cast iron from rain water leader to street. replace one electrical pull box at front of School</i>			0.00
4" no hub pipe		270	10.60	2,862.00
4" fittings		15	21.43	321.45
4"no hub coupling		50	12.58	629.00
1" copper pipe		190	4.35	826.50
copper fittings		12	6.15	73.80
cleanout box		1	68.10	68.10
traffic rated box w/ lid		1	293.00	293.00
Sand		12	48.00	576.00
off haul		1	750.00	750.00
dump fee		1	275.00	275.00
plumber		40	138.00	5,520.00
Laborer		16	90.00	1,440.00
Laborer		40	90.00	3,600.00
backhoe & operator		32	165.00	5,280.00
move on fee		1	450.00	450.00
overhead		1		3,399.60

Total	26,364.45
--------------	------------------