

Item #1

Cosumnes Oaks, Elk Grove, Monterey Trail and Sheldon High Schools – Replace water cannons; remove and dispose the existing heads and plumbing to 1.5” existing inlet pipe; supply and install new Christy box lids to set new heads; supply and install thrust blacks and secure heads per drawing; including debris haul off, clean up, and mobilization; to supply and install the following:

- Hunter ST-1600 HS-B adjustable 40-360 heads
- Hunter ICV-201G control valves
- Lasco 2” schedule 80 swing joints
- KBI 1.5” low torque, sch 80 ball valve
- Miscellaneous schedule 80 PVC adapters, sleeves and fittings.

Requested by Elk Grove Unified School District.

Time extension for this item: 16 days

ADD

\$146,628.80