



February 26, 2018

Attn: Mr. Michael Fisher  
Milpitas Unified School District  
1331 East Calaveras Boulevard  
Milpitas, CA 95035

Re: Milpitas High School – Main Breaker Replacement  
1285 Escuela Parkway  
Milpitas, CA 9035  
Estimate #: E180632R1

Dear Mr. Fisher,

We propose to furnish labor and material necessary to complete the electrical work discussed and listed below for the sum of **\$ 22,350.00.**

**Inclusions:**

- Remove and dispose of existing 3,000A main breaker in MSB during PG&E service shutdown
- Furnish and install reconditioned 3,000A, 480V, Type KSP-3000, manually operated, bolt on breaker with 3,000A current limiting fuses
- Test main breaker after installation for proper function
- Refer to attached invoice for breaker from RESA
- Lead time is 6-8 weeks after approval
- Includes one year warranty
- PG&E coordination and allowance of \$2,500 included to cover costs
- Work figured during premium hours, during PG&E scheduled shutdown

**Exclusions:**

- Permits, fees, or bond
- Service or repair work to switchboard not related to breaker replacement

Sincerely,  
*Atlas / Pellizzari Electric, Inc.*

Jordan Sink  
**Estimator / Project Manager**

**ATLAS/PELLIZZARI ELECTRIC, INC.**  
450 Howland Street - Redwood City, CA 94063  
(650) 364-1204 main (650) 364-6193 fax  
CCL# 375862