

Shadko Construction and Design

General Building/Electrical Contractor

Lic. # 958088

Phone (916) 417-3361

Job Name: Abraham Lincoln ES Electrical and Signage Installation

Scope of Work: S C & D proposes to furnish and install all labor and material necessary to complete the following itemized scopes of work:

- Excavate from building to proposed sign location at approx. depth of 14", install ½" RMC per code. Install MC cable from existing panel and interface with underground conduit at NEMA 3R junction box mounted on the side of the building. Pull #12 awg. thhn from pull box to sign location. Terminate and test.
- Excavate, set up, and pour concrete foundation per manufacturers specs. and applicable codes. Includes installation of rebar cages and anchor bolts.
- Procure new, owner furnished, sign from SRCS Warehouse, transport to site, and install per manufacturers specs. Contractor assumes that the sign comes completely assembled from the manufacturer and the only thing required is bolting to the new foundation and electrical termination/testing.
- Work to be performed during normal business hours.

Total Material and Labor \$ 22,525

Thank You,

Tim Shadko, Owner

Please sign and date below if preceding proposal is accepted. Payment in full will be due upon completion of scope of work.

Shadko Construction and Design

General Building/Electrical Contractor

Lic. # 958088

Phone (916) 417-3361

Job Name: Albert Biella ES Electrical and Signage Installation

Scope of Work: S C & D proposes to furnish and install all labor and material necessary to complete the following itemized scopes of work:

- Excavate from building to proposed sign location at approx. depth of 14", install ½" RMC per code. Install MC cable from existing panel and interface with underground conduit at NEMA 3R junction box mounted on the side of the building. Pull #12 awg. thhn from pull box to sign location. Terminate and test.
- Excavate, set up, and pour concrete foundation per manufacturers specs. and applicable codes. Includes installation of rebar cages and anchor bolts.
- Procure new, owner furnished, sign from SRCS Warehouse, transport to site, and install per manufacturers specs. Contractor assumes that the sign comes completely assembled from the manufacturer and the only thing required is bolting to the new foundation and electrical termination/testing.
- Work to be performed during normal business hours.

Total Material and Labor \$ 22,525

Thank You,

Tim Shadko, Owner

Please sign and date below if preceding proposal is accepted. Payment in full will be due upon completion of scope of work.

Shadko Construction and Design

General Building/Electrical Contractor

Lic. # 958088

Phone (916) 417-3361

Job Name: James Monroe ES Electrical and Signage Installation

Scope of Work: S C & D proposes to furnish and install all labor and material necessary to complete the following itemized scopes of work:

- Excavate from building to proposed sign location at approx. depth of 14", install ½" RMC per code. Install MC cable from existing panel and interface with underground conduit at NEMA 3R junction box mounted on the side of the building. Pull #12 awg. thhn from pull box to sign location. Terminate and test.
- Excavate, set up, and pour concrete foundation per manufacturers specs. and applicable codes. Includes installation of rebar cages and anchor bolts.
- Procure new, owner furnished, sign from SRCS Warehouse, transport to site, and install per manufacturers specs. Contractor assumes that the sign comes completely assembled from the manufacturer and the only thing required is bolting to the new foundation and electrical termination/testing.
- Work to be performed during normal business hours.

Total Material and Labor \$ 22,525

Thank You,

Tim Shadko, Owner

Please sign and date below if preceding proposal is accepted. Payment in full will be due upon completion of scope of work.

Shadko Construction and Design

General Building/Electrical Contractor

Lic. # 958088

Phone (916) 417-3361

Job Name: Helen Lehman ES Electrical and Signage Installation

Scope of Work: S C & D proposes to furnish and install all labor and material necessary to complete the following itemized scopes of work:

- Excavate from building to proposed sign location at approx. depth of 14", install ½" RMC per code. Install MC cable from existing panel and interface with underground conduit at NEMA 3R junction box mounted on the side of the building. Pull #12 awg. thhn from pull box to sign location. Terminate and test.
- Excavate, set up, and pour concrete foundation per manufacturers specs. and applicable codes. Includes installation of rebar cages and anchor bolts.
- Procure new, owner furnished, sign from SRCS Warehouse, transport to site, and install per manufacturers specs. Contractor assumes that the sign comes completely assembled from the manufacturer and the only thing required is bolting to the new foundation and electrical termination/testing.
- Work to be performed during normal business hours.

Total Material and Labor \$ 22,525

Thank You,

Tim Shadko, Owner

Please sign and date below if preceding proposal is accepted. Payment in full will be due upon completion of scope of work.

Shadko Construction and Design

General Building/Electrical Contractor

Lic. # 958088

Phone (916) 417-3361

Job Name: Herbert Slater Electrical and Signage Installation

Scope of Work: S C & D proposes to furnish and install all labor and materials necessary to complete the following itemized scopes of work:

- Excavate, set up, and pour concrete foundation per manufacturers specs. and applicable codes. Includes installation of rebar cages and anchor bolts.
- Extend existing 120V power from previous sign location to new sign location.
- Procure new, owner furnished, sign from SRCS Warehouse, transport to site, and install per manufacturers specs. Contractor assumes that the sign comes completely assembled from the manufacturer and the only thing required is bolting to the new foundation and electrical termination/testing.
- Work to be performed during normal business hours.

Total Material and Labor \$ 14,500

Thank You,

Tim Shadko, Owner

Please sign and date below if preceding proposal is accepted. Payment in full will be due upon completion of scope of work.

X _____